MINISTRY OF SUPPLY - DLRD(A)/RRE

| Specification MOS(A)/CV2219 | SECURITY | | | | |
|--|----------------|----------------|--|--|--|
| Issue 3 Dated 8.10.53 To be read in conjunction with K1001, excluding clauses 5.2 & 5.8. | Specification | Valve | | | |
| | UNCLASS IF IED | UNCLASS IF IED | | | |

Indicates a change

| TYPE OF VALVE - Transmitting tetrode CATHODE - Directly-heated thoristed tungsten | | MARKING See K1001/4 | |
|--|----------------------------------|------------------------|---|
| ENVELOPE - Metal-glass construction PROTOTYPE - Modified CV1114 | BASE See Drawing on Page 3 | | |
| Filament Voltage Filament Current Max. Anode Dissipation Max. Operating Frequency Max. Seal Temperature (V) (V) (A) (W) (MC/S) (MC/S) | 10.0 70.0 200 60 140 | Note A A,C B | CONNECTIONS & DIMENSIONS See Drawing on Page 3 |
| CAPACITANCES (pF) Anode to all other electrodes Grid to all other electrodes Anode to grid (max.) | 20 35 2 | | |

NOTES

- A. Adequate cooling of the filament leads and adjacent re-entrant portion of the envelope shall be provided by at least 10 cu. ft. of air per minute with a pressure drop in the order of 2 ins. of water.
- B. For this dissipation forced air cooling must be provided by at least 85 cu. ft. of air per minute with a pressure drop across the valve in the order of 2 ins. of water.
- C. The valve should be operated at a constant current of 70 amperes to ensure maximum life. Under these conditions the range of filament voltage will be 9.3 to 10.7 volts.

CV2219/3/1

Z.5328.R.

TESTS

To be performed in addition to those applicable in K1001

| - | Test Conditions | | | | | Test | | Limits Min. Max. | | No. Tested | No t e |
|---|--|---|--|-----------|-----------------------|---|------|---------------------|---------------------|---------------|---------------|
| ŀ | Forced air cooling for the filament leads and the anode shall be provided by not more than 10 cu. ft. and 85 cu. ft. of air per min. respectively with a pressure drop across the valve in the order of 2 ins. of water. | | | | | | | | | | |
| | Vf (V) | | Vg2 (V) Strapp connecto a negati supply | ted Ve | Ia (mA) A trace | Hot Flash Process Anode voltage to be maintained at 35 kV for a period of 5 minutes without further flashing. | | - | - | | 1,2 |
| | b 7.5 kV RF at 22 Mc/s applies screen and control grids. Anode connected to earth; not connected. Tp = 5 usecs; prf = 300. | | | | filament | Conditions to maintained for ute without br | | •• | 100% | 2 | |
| | c 10.0 | . 0 | 0 | 0 | 0 | If | (A) | 66.5 | 73.5 | 100% | |
| Ī | d 10.0 | 1.0 kV | 1.OkV | Set | 200 | Re vers e Ig | (mA) | . == | 1.0 | 100% | |
| T | e 10.0 | 1.0 kV | 1.0kV | Read | 200 | Vg1 | (V) | - 85 | -120 | 100% | |
| | f 10.0 | 1.0 kV reduced to 700V | 1.0kV reduced to 700V | l . | Maintained at 200 | Vg1 change | (V) | 48 | 64 | 1005 | |
| | g 10.0 | Strapped. F half sine w Tp = 2/used | aveform. | - | alue 6 kV, | IC | (A) | 70 | - | 100% | |
| | h See K1001/A3. | | | | | Capacitances Ca - all Cg - all Cag | (pF) | 16.0 26.3 | 24.0 43.7 2.0 | 255 (1) | |
| Γ | i Life | Test | | | | | | | | | |


j Life Test

A minimum life of 500 hours is to be expected. Life failure shall be considered to have occurred when the emission of the valve has fallen below 0.5A at Vf = 6.6V with Va, Vg2 and Vg1 = 300V.

NOTES

- 1. For this hot flash process there shall be a 300 ohn resistor in series with the applied volts and a capacitance of 0.25 µF in parallel with the supply volts on the supply side of the resistor.
- 2. Once the conditions specified have been met the test conditions need not be repeated for acceptance testing.

CV2219/3/2



CV 2219/3/3.